

Location: Pleasant Grove Middle School
2540 Green Valley Rd
Rescue, CA 95672

Job Name: Athletic Field Turf Replacement

Job Number: 16-0

Job Scope:

Description:

This is a renovation of the Athletic Departments existing field that will consist of removal off all existing turf/weeds, soil analysis to determine what amendments are needed to promote new turf, integration of soil amendments through ripping and tilling, leveling/grading and finish grading, and adjustment of existing sprinkler system before installing new sod turf.

Demolition: 66,500 sq. ft.

Remove existing turf/weeds

- a. Removal of all existing turf & weeds (no glyphosate or comparable herbicide to be used).
- b. Along existing track move existing sprinkler heads and any drains 10' out from fence on the North side of the field only.
- c. Remove existing turf and weeds and dispose of material off site.
- d. Rough grade and re-crown field to 1.5 % for adequate drainage.

Soil Preparation: 66,500 sq. ft.

- a. Use provided soil analysis from Sunland Analysis to determine quantities of recommended soil amendments and apply before ripping and rototilling into soil.
- b. Drag and apply finish crown of 1.5 % to field.
- c. Adjust irrigation system to provide adequate coverage for new turf.

New Turf: 66,500 sq. ft.

- a. Install fresh *Rhizomatous Tall Fescue (RTF)* form Sierra Sod, Inc. as per the growers recommendation
- b. Run irrigation system to make sure the new turf has adequate water coverage.

Special Notes:

Sod to be installed is a drought resistant blend *Rhizomatous Tall Fescue (RTF)*, grown by Sierra Sod, Inc.

This is a State Prevailing Wage Job

All contractors must have a valid State license A, & C-27

All contractors must be Registered with the Department of Industrial Relations and provide DIR#

No Glyphosate or comparable herbicide can be used on this project